

State of Wisconsin }
County of Forest } ss.


I L.E. George, do hereby certify that on the 21st day of October 19 75, I established the North one-sixteenth corner between Sections 1 and 6, T 34 N-R 12 & 13 E, Forth Principal Meridian. as described hereon

History: No record of this corner having ever been previously established.

Description of monument and accessories I established to perpetuate the location of this corner:
Galvanized iron pipe, three feet long, one inch in diameter, with Aluminum cap denoted as "Kimberly-Clark Corp. T35N N 1/16 Btwn 1 & 6 R12-13E George S 309 10-21-75"

The pipe is witnessed by:
Tamarack 8 S 40° W 19.4 feet. (Scribed S 1 BT)
Spruce 7 S 84° E 19.6 feet. (Scribed S 6 BT)

Description as to how corner was located: Quarter corner 1/4 mile South and a Witness corner to the Meander corner 10 chains North are set. Located North one-sixteenth corner 1313.7 feet North of the Quarter corner and on a straight line between the above noted corners.



O = Corner monument restored



Surveyor's Seal

Resident witnesses _____

Dated at Crandon, Wisconsin, this 28th day of October, 1975.

Signature L. Ernest George

Title Land Surveyor Registration No. S 309

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 27th day of May 19 77, and was filed in Book No. _____ Page No. _____ of County Records.

DOCUMENT NUMBER 111523

Signature Eugene Stutzman Title Register of Deeds

43412 13000

Index No.