

State of Wisconsin
County of FOREST

ss. ESTABLISHMENT OF QUARTER - QUARTER SECTION CORNER BETWEEN ORIGINAL GOVERNMENT SURVEY CORNERS.

I NEAL SPERHAKE, do hereby certify that on the FOURTEENTH day of SEPTEMBER, 19 64, I established the SOUTH ONE SIXTEENTH CORNER BETWEEN SECTIONS 3 AND 2, TOWNSHIP 34 NORTH, RANGE 13 EAST, Fourth Principal Meridian, as described hereon.

History: There is no record of this corner having ever been previously established.

Description of monument and accessories I established to perpetuate the location of this corner:


At the point determined for the location of the corner I emplaced a:

GALVANIZED IRON PIPE, THREE FEET LONG, ONE INCH IN DIAMETER, WITH ALUMINUM CAP DENOTED AS, "KIMBERLY CLARK CORP. T34N S 1/16 BTWN. 3 & 2 R13E SPERHAKE RLS 463 9/14/64."

The pipe is witnessed by:

- Oak 7 S 89°E 73 links. (SCRIBED S2 BT).
- W. Birch 9 N 53°W 74 links. (SCRIBED S3 BT).


Description as to how corner was located: Since both the quarter section corner 1/4 mile north and the section corner 1/4 mile south have been previously established with a distance between them of 40.06 chains, the S 1/16th. corner was set 20.03 chains from either corner and on a straight line between them.



0 = Corner monument restored

89570

REGISTERER'S OFFICE
FOREST COUNTY, WIS.



At 10 o'clock A.M.
Anna Peterson Register of Deeds

Resident witnesses _____

Dated at Crandon, Wisconsin, this 12 day of Jan., 19 65.

Signature Neal Sperhake

Title Registered Land Surveyor Registration No. 463

Office of _____ County of Forest
I hereby certify that the within instrument was signed & sworn to office for record on the 12 day of January 19 65, and was filed in Book No. _____ Page No. _____ of County Records.

Surveyor's Seal

Signature Anna Peterson Title Notary Public

43413031040

Index No. 8-17