

State of Wisconsin
County of FOREST

} ss. ESTABLISHMENT OF QUARTER - QUARTER SECTION CORNER BETWEEN ORIGINAL GOVERNMENT SURVEY CORNERS.

I NEAL SPERHAKE, do hereby certify that on the TWELFTH day of NOVEMBER, 19 63, I established the NORTH ONE SIXTEENTH CORNER BETWEEN SECTIONS 2 AND 3, TOWNSHIP 34 NORTH, RANGE 13 EAST, Fourth Principal Meridian, as described hereon.

History: There is no record of this corner having ever been previously established.

Description of monument and accessories I established to perpetuate the location of this corner:


At the point determined for the location of the corner I emplaced a:

GALVANIZED IRON PIPE, THREE FEET LONG, ONE INCH IN DIAMETER, WITH ALUMINUM CAP DENOTED AS, "KIMBERLY CLARK CORP. T34N N 1/16 BTWN. 2 & 3 R13E SPERHAKE RLS 463 11/12/63."

The pipe is witnessed by:

Maple 10 S 72°E 47 links. (SCRIBED S 2 BT).
Hemlock 10 N 74°W 37½ links. (SCRIBED S 3 BT).

Description as to how corner was located: The section corner ¼ mile north and the quarter corner ¼ mile south have been previously established with a distance of 37.46 chains between them. The record length of this line was 37.40 chains. The record length of the line between the quarter section corner and the north 1/16 corner between 2 and 3 was 20.00 chains. Thus, set the N 1/16 corner 20.03 chains north of the quarter corner between sections 2 and 3 and 17.43 chains south of the section corner between sections 2 and 3 on the town line and on a straight line between them.



O = Corner monument restored

Subscribed & sworn to before me this 25 day of Aug. 1964

Anna Peterson
Notary Public, Forest Co., Wis
Com. expires 10/31/65

88916

Resident witnesses _____

Dated at Crandon, Wisconsin, this 25 day of Aug., 1964.

Signature Neal Sperhake
Title Registered Land Surveyor Registration No. 463

Office of Reg. of Deeds County of Forest,
I hereby certify that the within instrument was filed in this office for record on the 25 day of Aug. 1964, and was filed in Book No. _____ Page No. _____ of County Records.)

Surveyor's Seal

Signature Anna Peterson Title Reg. of Deeds

43413033000

Index No.

8-17
B-17