

State of Wisconsin  
County of FOREST

} ss. ESTABLISHMENT OF QUARTER - QUARTER SECTION CORNER BETWEEN ORIGINAL GOVERNMENT SURVEY CORNERS.

I NEAL SPERHAKE, do hereby certify that on the NINETEENTH day of NOVEMBER, 1963, I established the EAST ONE SIXTEENTH CORNER BETWEEN SECTIONS 27 & 34, TOWNSHIP 34 NORTH, RANGE 13 EAST, Fourth Principal Meridian, as described hereon.

History: There is no record of this corner having ever been previously established.

Description of monument and accessories I established to perpetuate the location of this corner:


At the point determined for the location of the corner I emplaced a:

GALVANIZED IRON PIPE, THREE FEET LONG, ONE INCH IN DIAMETER, WITH ALUMINUM CAP DENOTED AS, "KIMBERLY CLARK CORP. T34N E 1/16 BTWN. 27 & 34 R13E SPERHAKE RLS 463 11/19/63."

The pipe is witnessed by:

- B. Ash 10 S 12°E 10 links. (SCRIBED S34 BT).
- Y. Birch 8 N 64°E 48 links. (SCRIBED S27 BT).

Description as to how corner was located: The section corner  $\frac{1}{4}$  mile east and the quarter corner  $\frac{1}{4}$  mile west have been previously established with a distance of 41.06 chains between them. Thus, set the E 1/16 corner 20.53 chains from either corner and on a straight line between them.



O = Corner monument restored

Subscribed & sworn to before me this 25 day Aug. 1964

*Anna Peterson*  
NOTARY PUBLIC, FOREST CO., WIS  
COM. EXPIRES 10/31/65

89005

Resident witnesses \_\_\_\_\_

Dated at Crandon, Wisconsin, this 25 day of Aug, 1964.

Signature *Neal Sperhake*

Title Registered Land Surveyor Registration No. 463

Office of Reg. of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 25 day of Aug 1964, and was filed in Book No. \_\_\_\_\_ Page No. \_\_\_\_\_ of County Records.

Surveyor's Seal

Signature *Anna Peterson* Title Reg. of Deeds

43413270010

Index No. V-116  
VI 6