

86993 ESTABLISHMENT OF QUARTER - QUARTER SECTION CORNER BETWEEN ORIGINAL GOVERNMENT SURVEY CORNERS

Index No. Z-12
712

STATE OF WISCONSIN
I NEAL SPERHAKE, do hereby certify that on the NINETEENTH day of NOVEMBER, 1962, I established the EAST ONE SIXTEENTH CORNER BETWEEN SECTIONS 4, TOWNSHIP 33 NORTH, RANGE 13 EAST, AND, 33, TOWNSHIP 34 NORTH, RANGE 13 EAST, Fourth Principal Meridian, as described hereon.

Resident Witnesses:
Richard Piontek - Waubeno.

This corner can also be described as either the, "EAST 1/8 TH, OR, THE EAST QUARTER-QUARTER SECTION CORNER BETWEEN SECTIONS 4, T33N-R13E, AND, 33, T34N-R13E, 4 TH P. M.

History:
There is no record of this corner having ever been previously established.


Description of monument and accessories I established to perpetuate the location of this corner.

At the point determined for the location of the corner I emplaced as:
"GALVANIZED IRON PIPE, THREE FEET LONG, ONE INCH IN DIAMETER, WITH AN ALUMINUM CAP DENOTED AS, 'KIMBERLY-CLARK CORP T33-34N E 1/16 BTWN 4 & 33 R13E SPERHAKE RLS 463 11-19-62".

The pipe is witnessed by:
Cedar 9 N 7°E 21 links. (Scribed S33 BT).
Cedar 8 S 7°W 20 links. (Scribed S 4 BT).


Description as to how corner was located:

Since both the quarter section corner one quarter mile west, and the section corner one quarter mile east have been previously established, with a distance between them of 40.01 1/2 chains, the 1/16 th corner was set 20.00 3/4 chains from either corner, on a straight line between them.



○ = Corner monument established

REGISTER'S OFFICE
FOREST COUNTY, WIS.



At 8 o'clock P.
Karl C. Linger Register of Deeds

Dated at Crandon, Wis., this 11th day of April, 19 63

Signature Neal Sperhake Title Registered Land Surveyor Registration No. S-463

Office of Register of Deeds, County of Forest, I hereby certify that the within instrument was signed and sworn to in the presence of on the 11th day of April, 19 63

at Crandon Wis.

Adeline De Noble
Notary (Register of Deeds) Public
Forest County, Wisconsin
By My commission expires February 6, 1966

My Commission Expires
February 6, 1966

Surveyor's Seal

43413330010