

# CERTIFIED LAND CORNER RESTORATION

Index No. **B-9**

State of Wisconsin }  
County of Forest } ss.


I Philip T. Hansen, do hereby  
certify that on the 24th day  
of May, 1977, I ~~found~~  
established ~~evidence of~~ the N 1/16  
corner of Section 4 & 5  
Township 35, North, Range  
12 East, Fourth Principal Meridian,  
as described hereon; and that from this evidence  
I established a new monument and accessories  
as described hereon to perpetuate the original  
location of this corner.

Resident witnesses:

Glen Barker

Jim Claflin

Herb Wagoner



○ = Corner monument restored.

History of original corner establishment:

No records available on any survey for this corner.

Description of corner evidence found:

No evidence of any corner or witness monuments.

Corner established by proportion. Ran traverse from Section Corner 4,5,8,9 North 4805.96 chains to Section Corner 32, 33, 4 and 5. From re-established 1/4 corner at 39.068 chains set N 1/16 corner at 19.532 chains north of 1/4 corner and 14.2195 chains S 2° 33' 52" E from Sec. 4,5,32,33.

Description of monument and accessories I established to perpetuate the original location of this corner.

Set 1 1/2" iron pipe with 2" brass cap stamped:

Monument projects 12" above ground.

Marked NBTs - Tamarack 7" S39°E, 30.2 links, scribed 1/16 BT.

Tamarack 6" N20°W, 48 links, scribed 1/16 BT.

S498  
T35N R12E  
N 1/16 S5 S4  
CPI-1977

Dated at Rhineland, Wis., this 31st day of May, 1977

Signature Philip T. Hansen Title Registered Land Surveyor Registration No. S-498  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within  
instrument was filed in this office for record on the 6th day of July, 1977  
at 3:30 o'clock P. M.

Eugene Stagny  
(Register of Deeds)

By \_\_\_\_\_ Deputy

DOCUMENT NUMBER  
**111811**