

State of Wisconsin
County of FOREST

ss. ESTABLISHMENT OF WEST QUARTER - QUARTER SECTION CORNER
OF SECTION 34

I L. ERNEST GEORGE, do hereby certify that on the THIRD day of JUNE,
19 68, I established the WEST ONE SIXTEENTH CORNER ON THE EAST-WEST QUARTER LINE OF
SECTION 34, TOWNSHIP 35 NORTH, RANGE 13 EAST, Fourth Principal Meridian,
as described hereon.

History: There is no record of this corner having ever been previously established


Description of monument and accessories I established to perpetuate the location of this corner:
At the point determined for the location of the corner, I emplaced a:

GALVANIZED IRON PIPE, THREE FEET LONG, ONE INCH IN DIAMETER, WITH ALUMINUM CAP DENOTED AS,
"KIMBERLY-CLARK CORP. T35N W 1/16 of SEC. 34 R13E GEORGE RLS S-0309 6/3/68."

The pipe is witnessed by:

- W. Birch 7 N 06°W 19½ links. (SCRIBED S34 BT).
- W. Birch 7 N 26°E 24½ links. (SCRIBED S34 BT).

Description as to how corner was located: The center quarter of section 34 has been previously
set and the location of the ¼ between section 33 and 34 has been
previously determined. There is 39.02¼ chains between these points.
Thus, set the west 1/16th corner of section 34, 19.51¼ chains from
either point and on a straight line between them. The west 1/16th
corner of section 34 is also 10.18-¾ chains east of an iron pipe
which is located on the east-west quarter line of section 34 and
45½ links east of the shoreline of Ground Hemlock Lake.



O = Corner monument
restored

Resident witnesses _____

DOCUMENT NUMBER
95964

Dated at Iron Mountain, Michigan, Wisconsin, this 20th
day of December, 1968.

Signature L. Ernest George
Title Registered Land Surveyor Registration No. S-0309

Office of Register of Deeds County of Forest
I hereby certify that the within instrument was filed in this
office for record on the 21st day of February
19 69, and was filed in Book No. I of Page No. X-14
of County Records. **CORNER RESTORATIONS**

Surveyor's Seal

Signature Eugene Stetson Title Register of Deeds

435 1334 2830

Index No. **X14**