

State of Wisconsin
County of FOREST

} ss. ESTABLISHMENT OF NORTH QUARTER - QUARTER SECTION CORNER
OF SECTION 34.

I L. ERNEST GEORGE, do hereby certify that on the THIRD day of JUNE,
19 68, I established the NORTH ONE SIXTEENTH CORNER ON THE NORTH-SOUTH QUARTER LINE OF
SECTION 34, TOWNSHIP 35 NORTH, RANGE 13 EAST, Fourth Principal Meridian,
as described hereon.

History: There is no record of this corner having ever been previously established.


Description of monument and accessories I established to perpetuate the location of this corner:
At the point determined for the location of the corner, I emplaced a:

GALVANIZED IRON PIPE, THREE FEET LONG, ONE INCH IN DIAMETER, WITH ALUMINUM CAP DENOTED AS,
"KIMBERLY-CLARK CORP. T35N N 1/16 of SEC. 34 R13E GEORGE RLS S-0309 6/3/68."

The pipe is witnessed by:

- Maple 6 S 03°E 12 links. (SCRIBED S34 BT).
- Maple 5 S 86°W 25 links. (SCRIBED S34 BT).

Description as to how corner was located: The quarter corner between sections 27 and 34
and the center 1/4 of section 34, have been previously established
with a distance of 40.87 chains between them. Thus, set the north
1/16th of section 34, 20.43½ chains from either corner and on a
straight line between them.



0 = Corner monument
restored

DOCUMENT NUMBER
95963

Resident witnesses _____

Dated at Iron Mountain, Michigan, Wisconsin, this 20th
day of December, 19 68.

Signature L. Ernest George

Title Registered Land Surveyor Registration No. S-0309

Office of Register of Deeds County of Forest,
I hereby certify that the within instrument was filed in this
office for record on the 21st day of February
19 69, and was filed in Book No. I of _____ Page No. W-15
of County Records. **CORNER RESTORATION**

Surveyor's Seal

Signature Eugene Staszny Title Register of Deeds

43513343020

Index No. **W15**