

CERTIFIED LAND CORNER RESTORATION

Index No. **83**

73

State of Wisconsin }
County of Forest } ss.

I, George V. Kapitz, do hereby certify that on the 30th day of November, 1961, I found evidence of the quarter corner of section 6 and 31 Township 34 and 35, North, Range 14 E, Fourth Principal Meridian, as described hereon; and that from this evidence I established ~~a new monument and~~ accessories as described hereon to perpetuate the ~~original~~ location of this corner.

Resident witnesses:

History of original corner establishment:
Surveyed by Alfred Millard in 1857
Dependent resurvey of section 6, T34N, R14E by Hugh B. Crawford in 1946
Set concrete monument, 24 ins. long, 6 ins. diam., 20 ins. in the ground,
With an iron post 23 ins. long, 1 in. diam. embedded in center, with Brass Cap Mkd.:


S 31 from which the following Bearing trees bear:
1/4 _____
1. Birch 10", N31° E, 37 lks.
2. Hemlock 20", S27 3/4° W, 45 lks.

S 6 -1946
Description of corner evidence found:
1. found concrete monument with brass cap marked as described above
2. Birch 13", N31° E, 24.7 ft.
3. Hemlock 20 1/2", S27 3/4 W, 29.70 ft.
4. Hemlock 11", S29° E, 10.20 ft., This B.T. is unrecorded and dead

Description of ~~monument and~~ accessories I established to perpetuate the ~~original~~ location of this corner.

- 1. Blazed and scribed y. Birch, 10", N28° W, 18.10 ft. (27 lks.)

FORM 985 R. C. MILLER CO., MILWAUKEE



○ = Corner monument ~~marked~~.

Dated at Grandon, Wis., this 24th day of January, 1962

Signature George V. Kapitz Title Land Surveyor Registration No. S-670
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within instrument was filed in this office for record on the 24th day of January, 1962 at 9 o'clock A. M.

Anna Peterson
(Register of Deeds) DOCUMENT NO. 85682

By _____ Deputy

43514310010