

State of Wisconsin }
County of FOREST } ss.

I L. ERNEST GEORGE, do hereby certify that on the SIXTEENTH day of OCTOBER, 19 68, I established the WEST ONE SIXTEENTH CORNER BETWEEN SECTION 32, TOWNSHIP 35 NORTH, RANGE 14 EAST AND SECTION 5, TOWNSHIP 34 NORTH, RANGE 14 EAST Fourth Principal Meridian. as described hereon.

History:

There is no record of this corner having ever been previously established.

Description of monument and accessories I established to perpetuate the location of this corner:


At the point determined for the location of the corner I emplaced a:

GALVANIZED IRON PIPE, THREE FEET LONG, ONE INCH IN DIAMETER, WITH ALUMINUM CAP DENOTED AS, "KIMBERLY-CLARK CORP. T34-35N W 1/16 BTWN. 32 & 5 R14E GEORGE S-0309 10/16/68."

This pipe is witnessed by:

Aspen 7 N 60 W 29 links. (SCRIBED S 32 BT)
Aspen 6 S 30 W 34 links. (SCRIBED S 5 BT)

Description as to how corner was located: The section corner $\frac{1}{4}$ mile west and the quarter corner $\frac{1}{4}$ mile east have been previously set with a distance of 39.97 chains between them. Thus set the W 1/16th corner 19.98 $\frac{1}{2}$ chains from either corner and on a straight line between them.



O = Corner monument restored

Resident witnesses _____

Dated at Crandon, Wisconsin, this 18th day of March, 19 74.

Signature L. Ernest George
Title Registered Land Surveyor Registration No. S-0309

Office of Register of Deeds County of Forest,
I hereby certify that the within instrument was filed in this office for record on the 19th day of March 19 74, and was filed in Book No. Corner Page No. A-6 of County Records. Restorations

DOCUMENT NUMBER 105005

Signature Eugene Stutzman Title Register of Deeds

Surveyor's Seal

43514320030

Index No. A 6