

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }
County of Forest } ss.

I Milo E. Stefan, do hereby certify that on the 21st day of October, 1982, I found evidence of the West 1/4 corner of Section 9 Township 35N, Range 15E, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Surveyed in 1859 by James McBride
40.00 chains, set 1/4 section wood post
Hemlock, 12", S70E, 20 lks., 13.2 feet
Hemlock, 16", N60W, 30 lks., 19.8 feet


Description of corner evidence found:

Found 5" x 5" x 2' Cedar post in mound of stone.
Hemlock stump, 18" - 20", N60W, 19.8 feet
Hemlock stump remains, S70E, 13.2 feet

Description of monument and accessories I established to perpetuate the location of this corner:

Placed a 2" x 30" aluminum pipe in mound of stone with cap stamped as follows:
T35N, R15E, S8, 1/4, S9, 1980, RLS-1558
From which the following bear:
Sugar Maple, 8", S30E, 10.70 feet
White Spruce, 5", S32W, 20.51 feet
White Spruce, 13", N43W, 32.39 feet
Steel sign post, NE, 1.4 feet

DOCUMENT NO.
124183



● - Corner monument restored
□ -

Resident witnesses.....

Dated at Rhinelander, Wisconsin, this 2 day of MAY 1982

Signature Milo E. Stefan Title Land Surveyor
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. RLS-1558

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 12th day of September 1983, and was filed in Book No. Page No. of County Records.

Signature Eugene Staszewski Title Register of Deeds

Township 35N, Range 15E, Section 9, Index No. G-9, Page No. 43

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }
 County of Forest } ss.

I Milo E. Stefan, do hereby certify that on the 21 day of October, 19 80, I found evidence of the West Quarter corner of Section 9 Township 35 North, Range 15 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Surveyed by James McBride in June 1859.
 Set Wood Post.
 Hemlock 12", S70°E, 20 lks.
 Hemlock 16", N60°W, 30 lks.

Description of corner evidence found:

Wood post in mound of rock
 Hemlock Stump remains S70°E, 13.2'
 Hemlock Stump remains N60°W, 19.8'


Description of monument and accessories I established to perpetuate the location of this corner:

At corner position set 2 inch by 30 inch aluminum pipe with cap stamped:
 T35N, R15E, 1/4, S8, S9, 1980, R.L.S. 1558

From which the following bear:

Sugar Maple 8", S30°E, 10.70'
 W. Spruce 5", S32°W, 20.51'
 W. Spruce 13", N43°W, 32.39'

DOCUMENT NO.
119861



● - Corner monument restored
 □ -

Resident witnesses.....

Dated at Laona Wisconsin, this 3 day of November 19 80.

Signature *Milo E. Stefan* Title Land Surveyor
 (County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. 1558

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 2nd day of June 19 81, and was filed in Book No. Page No. of County Records.

Signature *Eugene Stutzman* Title Register of Deeds

Township 35N, Range 15E, Section 9, Index No. G-9, Page No.

69