

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }  
 County of Forest } ss.

I, Milo E. Stefan, do hereby certify that on the 11th day of August, 1983, I found evidence of the North Quarter corner of Section 22 Township 35 North, Range 15 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Surveyed in 1859 by James McBride  
 39.75 chains, set wood post  
 Basswood, 14", S.36°E., 14 links, 9.24 feet  
 Sugar, 14", N.2°E., 20 links, 13.20 feet

Description of corner evidence found:


Basswood Sprouts, 10" - 12", S.36°E., 9 feet 11 inches  
 Stump Hole, N.2°E., 13 feet - 14 feet  
 Local Evidence: 1 1/2" x 4" iron pipe in large mound of stone with  
 4" x 4" x 30" rotted post

Description of monument and accessories I established to perpetuate the location of this corner:

Placed a 2" x 36" aluminum monument with tablet stamped as follows:  
 T35N, R15E, S15, 1/4, S22, 1983, RLS-1558  
 From which the following bear:  
 Sugar, 14", N.28°E., 30.41 feet  
 Sugar, 6", S.45°W., 24.29 feet  
 Basswood, 12", N.43°W., 23.05 feet  
 Steel Sign Post, Southwest, 2.80 feet



DOCUMENT NO.  
 124187



● - Corner monument restored  
 □ -

Resident witnesses.....

Dated at Rhinelander Wisconsin, this 12th day of September, 1983.

Signature *Milo E. Stefan* Title Land Surveyor  
 (County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. RLS-1558

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 12th day of September, 1983, and was filed in Book No. .... Page No. .... of County Records.

Signature *Eugene Stutzman* Title Register of Deeds

Township 35 North, Range 15 East, Section 22, Index No. N-15, Page No. B-2, P-77