

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin

County of Forest

ss.

I Jean F. Resvick, do hereby certify that on the 2nd day of June, 1965, I found evidence of the northwest section corner of section 1 Township 34 north, Range 15 east, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:


Surveyed in 1857 by Artemas Curtis. 80.00 chains west between section 1 and 36 set post.
 Tamarack 12, bears N67W, 64 lks.
 Tamarack 12, bears N43E, 32 lks.
 Tamarack 14, bears S57E, 42 lks.
 Tamarack 14, bears S34W, 30 lks.
 1.50 chains north leave swamp.
 8.25 chains west leave swamp
 21.00 chains south leave swamp
 18.00 chains east leave swamp

Description of corner evidence found:

Tamarack scribed fallen snag and stump. Old post point bears N57W, 21.1 ft. 91 ft. north leave swamp. 8.25 chains west leave swamp.

Description of monument and accessories I established to perpetuate the original location of this corner:

Replaced post point with a 2 inch inside diameter galvanized wrought iron pipe, 5 feet long, filled with concrete with brass cap marked.



From which the following blazed and scribed new bearing trees bear.

Cedar 6, bears N17E, 15.35 ft.
 Cedar 10, bears S80E, 25.43 ft.
 Cedar 9, bears S34W, 38.03 ft.
 Cedar 5, bears N51W, 34.58 ft.

Steel post 1.2 ft. SE of monument



Resident witnesses

Dated at Rhinelander Wisconsin, this 8th day of April 1970.

Signature Jean F. Resvick Title Cadastral Surveyor
 (County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802 DOCUMENT NUMBER 98035

Office of Register of Deeds County of Forest
 I hereby certify that the within instrument was filed in this office for record on the 22nd day of May 1970, and was filed in Book No. Page No. A-21 of County Records.

Signature Eugene Stetson Title Register of Deeds

Township 34 North, Range 15 East, Section 1, Index No. A-21, Page No.

4251535 0000

A
21