

# CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }  
County of Forest } ss.

I Jean F. Resvick, do hereby certify that on the 18th day of September, 1974, I found evidence of the East Quarter corner of Section 3 Township 35 North, Range 16 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

## Description of original monument and accessories and subsequent restorations:


Surveyed by James McBride August 1858.  
South corrected between Sections 2 and 3. 36.50 chains set post for corner of Sections 2 and 3.  
Sugar, 6", N79W, 33 lks  
Elm, 12", N66E, 21 lks  
16.50 chains north enter swamp E&W  
21.50 chains north stream 100 lks runs east

## Description of corner evidence found:


Iron pipe  
Sugar 24", N79°W 33 lks from pipe  
16.50 chains north to swamp  
21.50 chains north to north side of stream runs east

## Description of monument and accessories I established to perpetuate the location of this corner:

At the corner position set a 2 inch inside diameter galvanized pipe 3 feet long filled with concrete with a brass cap stamped: T35N, R16E, 1/4, S3, S2, 1975, S-802.  
From which the following bear  
Sugar 10" N14°E, 9.55 feet  
Sugar 7" N36°W, 22.48 feet  
Set a steel sign post southeast 0.50 feet



43516032000



● = Corner monument restored  
□ =

Resident witnesses

Dated at Rhinelander Wisconsin, this 20 day of March 1975.

Signature Jean F. Resvick Title Land Surveyor  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 31st day of March 1975, and was filed in Book No. Corner Restorations Page No. C-17 of County Records. Document Number 106868

Signature Eugene Stetson Title Register of Deeds

Township 35 North, Range 16 East, Section 3, Index No. C-17, Page No.

C 17