

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }
County of Forest } ss.

I, Jean F. Resvick, do hereby certify that on the 5 day of August, 1977, I found evidence of the South quarter corner of Section 19 Township 35 North, Range 16 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:



- Surveyed in 1858 by James McBride
- 52.50 chains east corrected between sections 19 and 30, set post.
- Yellow pine 8, N86W, 290 lks.
- White pine 12, S87W, 283 lks.
- 8.5 ch. west leave marsh, bears NE-SW
- 13.0 ch. east leave marsh, bears NW-SW

Description of corner evidence found:

- Yellow pine, 8 inch diameter when scribed
- 2 old posts found bear to yellow pine N89W, 283 lks.
- No evidence of 12" white pine found
- It is assumed that 50 years or more they had more evidence than is there today and being unable to find the white pine the post is accepted as found to be the corner.

Description of monument and accessories I established to perpetuate the location of this corner:

- Replaced old post point with 2 inch inside diameter galvanized iron pipe, 6 feet long, the top 3 feet filled with concrete with brass cap stamped: T35N, R16E, S19, 1/4, S30, 1977, S-802
- Blazed and scribed the following new bearing trees:
- Tamarack 9, N4W, 168.22 feet
- Tamarack 6, S15E, 141.40 feet
- Set steel sign post on north side of monument.
- Bearing trees are near north and south edges of swamp respectively



● - Corner monument restored
 □ -

Resident witnesses.....

Dated at Rhinelander Wisconsin, this 9 day of August 1977.

Signature *Jean F. Resvick* Title Land Surveyor
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802 DOCUMENT NUMBER 113297

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 13th day of February 1978, and was filed in Book No. Page No. of County Records.

Signature *Eugene Staszny* Title Register of Deeds

Township 35 North, Range 16 East, Section 19, Index No. R-3, Page No.

4351619002P

R
3