

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }
County of Forest } ss.

I Milo E. Stefan, do hereby certify that on the 5 day of September, 1979, I found evidence of the Northeast Section corner of Section 27 Township 35 North, Range 16 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Surveyed by James McBride in August 1858.
Set Post for Section Corner.
Birch 24", N84°E, 27 lks.
Elm 15", S48°E, 36 lks.
Sugar 8", S10°W, 15 lks.
Sugar 10", N86°W, 26 lks.

Description of corner evidence found:

Mound of stone with post hole, 20" in ground.
Decayed sugar stump, N86°W, 26 lks.
Stump hole, N84°E, 27 lks.
Stump hole, S48°E, 36 lks.
New Sugar BT's 12 - 15 years ago, no record available.


Description of monument and accessories I established to perpetuate the location of this corner:

Placed a 2 inch inside diameter galvanized iron pipe 30 inch long in post hole, concrete filled, with brass cap stamped:
T35N, R16E, S22, S23, S26, S27, 1979, S-1558. Replaced mound of stone.

From which the following bear:

Hemlock 20", N24°E, 92.63'
*Sugar Maple 10", S48°E, 7.38'
Hemlock 18", S31°W, 22.28'
*Sugar Maple 10", N82°W, 6.72'
Steel sign post, N45°W, 1.0'
*BT's scribed 12 - 15 years ago.

DOCUMENT NO.
119859



● - Corner monument restored
□ -

Resident witnesses.....

Dated at Laona Wisconsin, this 3 day of November 1980.

Signature Milo E. Stefan Title Land Surveyor
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-1558

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 2nd day of June 1981, and was filed in Book No. Page No. of County Records.

Signature Eugene Staszewski Title Register of Deeds

Township 35N, Range 16E, Section 27, Index No. R-17, Page No.

4351622

R17