


CERTIFIED LAND CORNER RESTORATION

Index No. **D 1**

State of Wisconsin } ss.
County of Forest

I Philip T. Hansen, do hereby
certify that on the 10th day
of December, 1974, I found
evidence of the S-1/16
corner of 1 and 6
Township 36, North, Range
11 & 12 East, Fourth, Principal Meridian,
as described hereon; and that from this evidence
I established a new monument and accessories
as described hereon to perpetuate the original
location of this corner.

Resident witnesses:



○ = Corner monument restored.

History of original corner establishment:

H.C. Lawrence recovered an old 1/16 corner of unknown origin when he ran a line from the E-1/4 corner to the Section Corner in 1957. The distance between the E-1/4 corner and the Section Corner was 10 links short of the original measurement. Both the 1/4 corner and Section Corner were recovered and checked distances to B.T.'s established by B.F. Dorr's survey of 1898. A new 4" cedar post was set at the S-1/16 corner 19.95 chains, equidistant between the 1/4 corner and Section Corner.

New B.T.'s Yellow birch 20" N87W 53½ links
 Sugar 11" S18E 28 links

Description of corner evidence found:

Recovered H.C. Lawrence 4" cedar post, squared and scribed S1-1/16 S6-1/16 in poor condition, tied to a 1" iron pipe. Recovered old bearing trees.

Yellow birch 20" N86W 53½ links scribed S B.T.
Sugar maple 11" S17E 27½ links scribed S-1/16

Description of monument and accessories I established to perpetuate the original location of this corner.

Set 1" x 5' iron pipe with 2" brass cap stamped -

No new B.T. established.

S498
T36N
S1 | S6
S-1/16

CPI-1974

Dated at Rhineland, Wis., this 6th day of January, 1975.

Signature Philip T. Hansen Title Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within instrument was filed in this office for record on the 17th day of March, 1975 at 3:35 o'clock P. M.

Eugene Stutzman
(Register of Deeds)

By _____ Deputy

Document No. **106810**

FORM 985 H. C. MILLER CO., MILWAUKEE

4361101000