

CERTIFIED LAND CORNER RESTORATION

Index No. C 1


State of Wisconsin }  
 County of Forest } ss.

I Philip T. Hansen, do hereby certify that on the 6th day of December, 1974, I found evidence of the 1/4 corner of 1-6 Township 37, North, Range 11 & 12 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:



FORM 985 H. C. MILLER CO., MILWAUKEE



○ = Corner monument restored.

History of original corner establishment:

Original corner established by William E. Dougherty, Government Deputy Surveyor, in 1859.

Elm 7" N50W 6 links  
 Elm 12" S70E 46 links

Retracement survey by H.C. Lawrence, 1950. Recovered old hardwood post, squared and scribed. Also recovered an 18" elm N50W 6 links. No trace of 12" elm.

Set new B.T.'s  
 Elm 12" N20W 22½ links  
 Elm 10" East 28 links  
 Maple 24" S70E 26 links

Description of corner evidence found:

Recovered 4" cedar post, squared and scribed S1¼ S6 - fair condition. Recovered 1" iron pipe set beside squared post.

B.T.  
 Elm 22" N50W 6 links  
 Elm 18" N20W 22½ links  
 Elm 15" N88E 28 links  
 R. Maple S70E 26 links  
 28"

Description of monument and accessories I established to perpetuate the original location of this corner.

Set 2-1/2" x 5' galvanized iron pipe with brass cap, stamped as follows:  
 Projecting 2-1/2' above ground.

Blazed and scribed B.T.  
 Sugar maple 10" S10W 50 links

S498  
 T36N  
 R11E S1 S6 R12E  
 1/4

CPI-1974

Dated at Argonne, Wis., this 30th day of December, 1974.

Signature Philip T. Hansen Title Registered Land Surveyor Registration No. S-498  
 (County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within instrument was filed in this office for record on the 17th day of March, 1975 at 3:35 o'clock P.M.

Eugene Stutzman  
 (Register of Deeds)

By \_\_\_\_\_ Deputy

43611012600