

CERTIFIED LAND CORNER RESTORATION

Index No. H 1

State of Wisconsin }
County of Forest } ss.

I Philip T. Hansen, do hereby certify that on the 30th day of December, 1974, I found evidence of the S-1/16 corner of Secs. 7 & 12 Township 36, North, Range 11 & 12 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:


.....
.....
.....

History of original corner establishment:
Retracement survey made by H.C. Lawrence, Reg. Surveyor, 1956 indicates he ran south on Random Line (Mag.) from B.F. Dorr's 1/4 corner, which he recovered a distance of 39.82 chains, to a point 95 links west of the Section Corner (Gov. original). He set the S-1/16 corner on line, equidistant between the 1/4 corner and Section Corner at 19.91 chains. Set 4" cedar post and BT sugar maple 10" S60E 16 links.

Description of corner evidence found:
Recovered H.C. Lawrence's 4" cedar post, squared and scribed S-1/16 S12; S-1/16 S7, in poor condition.
Old BT sugar maple 11" S60E 16 links recovered in good condition.

Description of monument and accessories I established to perpetuate the original location of this corner.
Set a 1" x 5' galvanized iron pipe with brass cap stamped as follows:

New BT's B. cherry 7" S48°W. 32½ lks. Scribed 1/16 BT
 S. maple 11" N13°E. 69½ lks. Scribed 1/16 BT



DOCUMENT NUMBER ----- **106953**

Dated at Rhineland, Wis., this 16th day of April, 1975.


Signature Philip T. Hansen Title Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within instrument was filed in this office for record on the 16th day of April, 1975 at 3:00 o'clock P. M.

Eugene Staszny
(Register of Deeds)

By..... Deputy

FORM 985 H. C. MILLER CO., MILWAUKEE



○ = Corner monument restored.

4361121000