

CERTIFIED LAND CORNER RESTORATION
U.S. PUBLIC LAND SURVEY

Index No. J-9

State of Wisconsin }
County of Forest } ss.

I Glen Barker, do hereby certify that on the 11th day of December, 19 87, I found evidence of the Section ~~8~~ corner of 8-9-16-17 Township 37N, North, Range 14 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

N. Spiess

H. Wagoner

History of original corner establishment:

Original corner established by J.L. Nowlin, Deputy Surveyor, in 1865, from from which cedar 12" bears N64°W 20 lks and Birch 8" bears S75°E 22 lks.

Description of corner evidence found:

Recovered remains of old wood post point buried in muck, also a very old beaver blaze on cedar 10" N3°E 23.15'. Old CPI type maps indicate this being the same position Ray Leigh long time forester for CPI Maintained.

Description of monument and accessories I established to perpetuate the original location of this corner.

Set a 2 1/4" Forest County aluminum monument with 3 1/4" alloy cap stamped:

Monument projects 18" above ground

Marked NBT's


Cedar 12" N43°E 29.16'
Black Ash 6" S47°E 21.78'
Black Ash 5" N80°W 9.07'
Scribed old beaver blaze on cedar 10" N3°E 23.15'.

T37N R14E

S8	S9
S17	S16

1987

S1682



○ = Corner monument restored.

Dated at _____, Wis., this _____ day of _____, 19_____

Signature Glen Barker Title Surveyor Registration No. 1082
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within instrument was filed in this office for record on the 18th day of May, 1988 at 1:05 o'clock P. M.

Paul Aschwendt
(Register of Deeds)

By _____ Deputy

DOCUMENT NUMBER
135245

FORM 985 H. C. MILLER CO., MILWAUKEE

43714080000

(e) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?
Perpetuated Location

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?

(i) I, Glen Barker
(type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Glen Barker
Signature

MAY 18, 1988
Date

