

CERTIFIED LAND CORNER RESTORATION

W-11 Index No. **W11**


State of Wisconsin }
County of Forest } ss.

I Philip T. Hansen, do hereby certify that on the 3rd day of October, 1975, I found evidence of the NC-1/16 corner of Section 33 Township 37, North, Range 14 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.


Resident witnesses:

Glen Barker

Jim Claflin



T37N R14E



○ = Corner monument restored.

History of original corner establishment: Corner established by I.R. Ritter, County Surveyor, in 1921. Set 3" cedar post, squared and scribed, from which Spruce 6" bears N5°E 11 links, and Cedar 10" bears S30°W 46 links.

Description of corner evidence found: Recovered 3" cedar post, squared and scribed 1/8 S, 1/8 S, in poor condition but still standing.

Recovered OBT's - Spruce 6" N5°E (N3°E) 11 links, now blown down, scribed 1/8 S BT.
Cedar 10" (12") S30°W (S33°W) 46 links, green, scribing grown over.

Description of monument and accessories I established to perpetuate the original location of this corner. Replaced 3" cedar post with 1 1/2" O.D. x 5' iron pipe with 2" brass cap stamped -

NBT's - Cedar 8" North 40.6 links, scribed 1/16 BT.
Cedar 6" S41°E 58.2 links, scribed 1/16 BT.

Iron pipe and BT's painted blue.

S498
T37N R14E
NC-1/16 S 33
1975

Dated at Argonne, Wis., this 9th day of October, 1975.

Signature *Philip T. Hansen* Title Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within instrument was filed in this office for record on the 16th day of October, 1975, at 2:30 o'clock P.M.

Eugene Staszny
(Register of Deeds)
By _____ Deputy

DOCUMENT NUMBER **108001**

FORM 985 H. C. MILLER CO., MILWAUKEE

43714333020