

CERTIFIED LAND CORNER RESTORATION



State of Wisconsin

County of Forest

ss.

I, Philip T. Hansen, do hereby certify that on the 25 day of September, 1975, I found evidence of the Quarter corner of Section 34 and 35 Township 37 North Range 14 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations: Original corner established by James L. Nowlin, Gov. Deputy Surveyor in 1865, from which cedar 12" bears N 14° E 35 lks and sugar 8" bears N 40° W 38 lks. Corner recovered and restored by J. R. Ritter, County Surveyor, in 1921, set new cedar post and established NBT'S - Aspen 8" S 15° E and Birch 7" N 80° W 13½ lks. Corner recovered by Ray Leigh, Consolidated Forester, in 1948. Recovered Ritters cedar post set new 1½" iron pipe.

Description of corner evidence found: Recovered 1½" iron pipe with rock mound, piled around base, in good condition.

No trace of old BTs visible


Description of monument and accessories I established to perpetuate the location of this corner: Replaced 1½" iron pipe with 2½" x 30" Berntsen, A-1 Federal Monument, Aluminum pipe with magnet installed in capand base. Pipe projects 6" above ground. Cap stamped. Set 1½" iron pipe beside new pipe and replace mound of rock around base.

NBTs Red Maple 10" S 5° E 24 lks scribed ¼ BT  
Cedar 8" S 54° W 61.7 lks scribed ¼ BT

Pipe and NBTs painted blue

S-498  
T 37 N R 14E  
S34 | S35  
1/4  
1975

T 37 N R 14 E



● - Corner monument restored  
□ -

Resident witnesses Glen Barker and Jim Claflin

Dated at Argonne Wisconsin, this 29 day of September 19 75

Signature Philip T. Hansen Title Registered Land Surveyor  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-498

DOCUMENT NUMBER **107923**

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 6th day of October 19 75, and was filed in Book No.          Page No.          of County Records.

Signature Eugene Stetson Title Register of Deeds

Township 37 North, Range 14 East Section 34 Index No.         , Page No.         

43714342000

X-17

X17