

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }
County of Forest } ss.

I Milo E. Stefan, do hereby certify that on the 28th day of July, 1983, I found evidence of the North Quarter corner of Section 11 Township 37 North Range 15 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Surveyed in 1865 by J. L. Nowlin
40.25 chains, set wood post
Spruce, 12", N.66°W., 35 links, 23.10 feet
Hemlock, 15", S.25°W., 12 links, 7.92 feet


Description of corner evidence found:

Hemlock stump, S.25°W., 8.00 feet
Local Evidence: Plantation post and charred Pine post mark the E 1/16

Description of monument and accessories I established to perpetuate the location of this corner:

Placed a 2" x 36" aluminum monument in mound of stone with tablet stamped as follows:
T.37N., R.15E., S2, 1/4, S11, 1983, RLS-1558
From which the following bear:
Red Maple, 4", S.36°E., 91.20 feet
White Pine, 14", S.1°E., 172.55 feet
Red Maple, 4", S.36°W., 74.78 feet
Steel Sign Post, S.75°W., 1.50 feet

DOCUMENT NO.
124206



● - Corner monument restored
□ -

Resident witnesses.....

Dated at Rhinelander Wisconsin, this day of 1983..

Signature Milo E. Stefan Title Land Surveyor
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. RLS-1558

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 13th day of September 1983, and was filed in Book No. Page No. of County Records.

Signature Eugene Staszny Title Register of Deeds

Township 37 North, Range 15 East, Section 11, Index No. E-19, Page No. B-3, P-78