

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }
County of Forest } ss.



I Jean F. Resvick, do hereby certify that on the 22nd day of August, 1973, I found evidence of the East One Sixteenth corner of Section 10 and 15 Township 37 North, Range 16 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:
Survey by F. R. Wincentzen of Genisot Engineering Co. in 1954
Set iron pipe with brass cap and scribed the following bearing trees.
White Pine 12, N78E, 4 lks.
White Pine 14, N22W, 17.7 lks.

Description of corner evidence found:
White Pine 19 inch diameter scribed.
White Pine 14 inch diameter scribed.
At a point 11.68 ft from 19 inch white pine and 2.64 ft from 14 inch, White Pine bearing to 19 inch white pine reads N28W and N78E to 14 inch white pine.

Description of monument and accessories I established to perpetuate the original location of this corner:
At this point of record distances from bearing trees
Set 2 inch diameter, galvanized iron pipe, 3 feet long
With brass cap stamped T.37N., R.16E., E 1/16, S10, S15, 1973, S-802.
White Pine 19, N28W, 17.7 lks.
White Pine 14, N78E, 4.0 lks.

43716100010



● = Corner monument restored
□ =

Resident witnesses.....
Dated at Rhinelander Wisconsin, this 1973 day of.....
Signature Jean F. Resvick Title Land Surveyor
(County Surveyor, Registered Land Surveyor, or other duly authorized official)
Surveyors Registration No. S-802 DOCUMENT NUMBER 104446
Office of Register of Deeds County of Forest
I hereby certify that the within instrument was filed in this office for record on the 13th day of November 1973, and was filed in Book No. Corner Restorations Page No. J-16 of County Records.

Signature Eugene Stegany Title Register of Deeds

Township 37 North, Range 16 East, Section 10, Index No. J-16, Page No.

J II