

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }
County of Forest } ss.

I William B. Cochrane, do hereby certify that on the 28 day of April, 19 77, I found evidence of the East Quarter corner of Section 10 Township 37 North, Range 16 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:


Surveyed in 1859 by James McBride
North between sections 10 and 11. 40.0 chains set quarter section post.
Tamarack, 10, N18°E, 24 lks.
Tamarack, 12, S42°W, 18 lks.

Description of corner evidence found:


Fallen tamarack, 12" diameter, scribed: 1/4S and BT
At a point N42°E, 18 lks. from the above bearing tree, a tamarack stump bears N18°E, 24 lks.
No evidence of a post was found

Description of monument and accessories I established to perpetuate the location of this corner:

At a point from the recorded distances and bearings of the original evidence found, I set a 2 inch inside diameter, galvanized pipe, 5 feet long, filled with concrete with a brass cap stamped: T37N, R16E, 1/4, S10, S11, 1977, S-1107
From which the following bear:
Cedar, 7", N50°E, 13.45 ft.
Black spruce, 5", S26°E, 27.77 ft.
Steel sign post, 1.0 ft. West



43716102000



● - Corner monument restored
□ -

Resident witnesses.....

Dated at Laona Wisconsin, this 21 day of July 19 77.

Signature William B. Cochrane Title Survey Technician
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-1107 DOCUMENT NUMBER 113304

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 13th day of February 19 78, and was filed in Book No. Page No. of County Records.

Signature Eugene Stutz Title Register of Deeds

Township 37 North, Range 16 East, Section 10, Index No. G-17, Page No.

G 17