

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin

County of Forest

ss.

I Jean F. Resvick, do hereby certify that on the 11 day of March, 19 74, I found evidence of the Northwest section corner of section 14 Township 38 north, Range 12 east, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Dependent resurvey in 1937 by Wesson Cook

From the remains of original evidence, set a concrete monument, 24 ins. long, 6 ins. in diam., 20 ins. in the ground, for the corner of sections 10, 11, 14 and 15, with a brass cap marked: T38N, R12E, S10, S11, S14, S15, 1937

From which: Spruce, 7" bears N66° 45'E, 23 lks.
 Spruce, 10", bears S70° 45'E, 28 lks.
 Spruce, 8" bears S65° 30'W, 15 lks.
 Spruce, 9" bears N5°W, 45 lks.

Description of corner evidence found:

Concrete monument as described above in place

No evidence of the NE bearing tree found.

Spruce stump, scricing visible, 12", S70°E, 28 lks.

Spruce stump, rotted mound, S65°W, 15 lks.


Spruce stump, scribing visible, 12", N5°W, 45 lks.

Description of monument and accessories I established to perpetuate the location of this corner:

Blazed and scribed the following new bearing trees:

Spruce, 4", N52°E, 17.33 ft.
 Balsam, 5", S70°E, 15.61 ft.
 Tamarack, 8" S22°W, 12.11 ft.
 Tamarack, 7", N45°W, 5.72 ft.

Set a steel sign post north and alongside the monument



● - Corner monument restored

□ -

Resident witnesses.....

Dated at RhinelandWisconsin, this 17 day of May19 74Signature Jean F. ResvickTitle Land Surveyor

(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802DOCUMENT NUMBER 105811Office of REGISTER OF DEEDS County of FOREST

I hereby certify that the within instrument was filed in this office for record on the 8TH day of AUGUST, 19 74, and was filed in Book No. RESTORATIONS Page No. 5-17 of County Records.

Signature Eugene D. StetsonTitle REGISTER OF DEEDSTownship 38 northRange 12 eastSection 14Index No. J-17Page No. 5

43812100000

