

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin

County of Forest

ss.

I, Jean F. Resvick, do hereby certify that on the 9th day of May, 1973,
~~XXXXXX~~ established the east quarter corner of Section 5
 Township 38 north, Range 14 east, Fourth Principal Meridian, as described
 hereon; and that ~~XXXXXX~~ I established a new monument and accessories as described hereon to per-
 petuate ~~XXXXXX~~ location of this corner:

Description of original monument and accessories and subsequent restorations:


Surveyed in 1865 by H. & J.L. Nowlin
 41.90 chains south corrected between sections 4 & 5, set post
 Cedar 10, S89E, 14 lks.
 Cedar 6, N68W, 15 lks.

Description of corner evidence found:

2 x 4 Cedar post, not scribed about 30 years old.
 Forest Service location poster on Cedar facing south dated 1957 and 1958
 post is of Forest Service origin and appears to be set at a proportional distance but
 not on line between section corners.
 The distance between section corners measured 5176.04 feet on a magnetic bearing of
 N01°58'E.

Description of monument and accessories I established to perpetuate the ~~original~~ location of this corner:

At the proportional distance of 2527.98 feet north on line between Section corner,
 set a 2 inch inside diameter, galvanized iron pipe, 3 feet long, filled with concrete
 to weigh 5 pounds per foot with brass cap stamped:




Blazed and scribed the following new bearing trees:

Maple 7, S31E, 17.48 feet

Maple 9, N78W, 39.05 feet

Set sign post 1.5 feet, northwest of monument
 North 1/2 mile measures 2648.06 feet



Resident witnesses

Dated at Rhineland Wisconsin, this 30th day of Aug,
 1973.

Signature Jean F. Resvick Title Land Surveyor
 (County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. 5-802

DOCUMENT NUMBER
104449

Office of REGISTER OF DEEDS County of FOREST

I hereby certify that the within instrument was filed in this office for record
 on the 13th day of November, 1973, and was filed in Book
 No. C-9 Page No. C-9 of County Records.

Signature Eugene Stutzman Title Register of Deeds

Township 38 north, Range 14 east, Section 5, Index No. C-9, Page No. C-9

43814052000