

CERTIFIED LAND CORNER RESTORATION

Index No. U-8


State of Wisconsin }
County of Forest } ss.

I Glen Barker, do hereby certify that on the 21st day of December, 1984, I found ~~existence of the~~ SE 1/16 corner of Section 29 Township 38, North, Range 14 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

N. Spiess

R. Lundt



○ = Corner monument restored.

History of original corner establishment:

A 1-1/4" well point bears N88E 83.16' of new established monument. Well point sets in old camp site. I believe it to be a fixture of the camp.

Description of corner evidence found:

Corner established by subdivision of SE 1/4 section 29. Location of SE 1/16 is 1329.86 of SC 1/16 and 1315.73' of EC 1/16.

Description of monument and accessories I established to perpetuate the original location of this corner.

Set a 1" iron pipe with 2" diameter alloy cap stamped: Monument projects 12" above ground.

Marked NBTs: Maple 5" N28E 49.94'
Red Pine N83W 59.09'

S1682
T38N
SE 1/16 S 29
R14E
CPI-1984

Dated at Rhineland, Wis., this 17th day of April, 1985

Signature Glen Barker Title Registered Land Surveyor Registration No. S1682
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within instrument was filed in this office for record on the 3rd day of May, 1985 at 11:30 o'clock A. M.

Paul Aschenbrenner
(Register of Deeds)

By.....Deputy

Document Number 127964

FORM 985 R. C. MILLER CO., MILWAUKEE

43814291010