


CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }
County of Forest } ss.

I, Jean F. Resvick, do hereby certify that on the 12 day of July, 19 67, I found evidence of the West quarter corner of Section 18 Township 39 North, Range 12 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Surveyed in 1859 by William E. Daugherty. Dependent resurvey in 1939 by Hal D. Craig. Set a concrete monument, 24 ins. long, 6 ins. dia., 18 ins. in the ground for the 1/4 sec. corner with brass cap marked:




- from which:
A pine snag, 12 in. dia., bears S28E, 21 lks.
A stump hole, bears N58W, 39 lks.
A jack pine, 5 in. dia., bears S16°30'E, 50 lks.
A Norway, 12 in. dia., bears S80W, 66 lks.

Description of corner evidence found:

- Monument as described and in place.
A jack pine snag, 5 in. dia., bears S16°E, 33.00 ft.
A red pine snag, 12 in. dia., bears S80W, 43.56 ft.
A pine snag, 12" dia., bears S28°E, 13.86 ft.

Description of monument and accessories I established to perpetuate the original location of this corner:

- Blazed and scribed the following new bearing trees:
A red pine, 14 in. dia., N36° 30'W, 102.50 ft. or 155.30 lks.
A red pine, 10 in. dia., S40W, 55.84 ft. or 84.60 lks.
Set 4x4 cedar post, 4 ft. above ground by monument.



● = Corner monument restored
□ =

Resident witnesses.....

Dated at Rhinelander Wisconsin, this 21st day of Feb. 19 68.

Signature: Jean F. Resvick Title: Cadastral Surveyor
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802 DOC. NO. 94229

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 27th day of February 19 68., and was filed in Book No. I. Page No. of County Records.

Signature: Eugene Stetson Title: Register of Deeds

Township 39 North, Range 12 East, Section 18, Index No. L-1, Page No.

43911132000