

U.S. PUBLIC LAND SURVEY MONUMENT RECORD


Index No. Z 9

State of Wisconsin }
County of Forest } ss.

I, John H. Fisher, do hereby certify that on the 29 day of January, 1985, I found evidence of the Southeast corner of Section 32 Township 39, North, Range 12 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

None



○ = Corner monument restored.

History of original corner establishment: Original survey in 1857 by Alfred Millard: Dependent resurvey in 1937 by Wesson Cook; at 39.55 the corner of Sections 4, 5, 32 and 33, which is marked by a Tamarack post, 4 x 4 3/8 inches above ground, set concrete monument 54 inches long 6 inches diameter 36 inches in ground in 12 inches of water, reinforced with an iron post 3 feet long, 2 inch diameter with brass cap stamped.


From which the following bear.

Original:

Tamarack 12" N7°E 20 lks
Fallen Tamarack 14" S81°W 26 lks
Tamarack stump 14" N45°W 44 lks

New Bearing Trees:

Balsam 10" N8-1/2°E 181 lks
Balsam 6" N47°W 208 lks



Description of corner evidence found:

B.L.M. Monument as described

Wood sign post S60°W 1.1 feet

Description of monument and accessories I established to perpetuate the original location of this corner.

Blazed and scribed the following new bearing trees:

| | | | |
|--------------|-----|-------|------------|
| White Spruce | 20" | N41°E | 216.0 feet |
| White Spruce | 10" | N 6°E | 172.5 feet |
| Red Pine | 12" | N21°W | 211.5 feet |
| Tamarack | 10" | N52°W | 153.0 feet |

Dated at Minocqua, Wis., this 21st day of March, 1985.

Signature John H. Fisher Title Registered Land Surveyor Registration No. S-836
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within instrument was filed in this office for record on the 24th day of July, 1985 at 1:10 o'clock P. M.

Paul Ascherbauer
(Register of Deeds)

By _____ Deputy

FORM NO. 985-A

H.C. Miller Company
Manufacturers

Stock No. 26273

DOCUMENT NUMBER 128457

~~128456~~

43912320000

