

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }  
County of Forest } ss.

I, Jean F. Resvick, do hereby certify that on the 30th day of September, 1974, I found evidence of the west quarter corner of Section 19 Township 40 North, Range 12 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:



Survey in 1857 by Alfred Millard  
Dependent Resurvey in 1926 by Guy R. Veal  
Set iron post 3 feet long, 2 inches diameter with brass cap marked: 1/4, S24, S19, 1926  
Hemlock 16, S16°45'E, 15 lks  
Hemlock 18, N40°00'W, 31 lks

Description of corner evidence found:

Monument as described above  
Hemlock 22, S17°E, 10.5 feet  
Hemlock stump 20, N40W, 20.5 feet

Description of monument and accessories I established to perpetuate the location of this corner:

Blazed and scribed new bearing tree  
Hemlock 22, N5W, 13.73 feet  
Set steel sign post 0.5 feet west of monument



● - Corner monument restored  
□ -

Resident witnesses.....

Dated at Rhinelander Wisconsin, this 20 day of March, 1975.

Signature *Jean F. Resvick* Title Land Surveyor  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802 Document Number 106877

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 31st day of March, 1975, and was filed in Book No. Corner Restorations Page No. P-1 of County Records.

Signature *Eugene Stutzman* Title Register of Deeds

Township 40 North, Range 12 East, Section 19, Index No. P-1, Page No. P 1

44011242000