

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }  
County of Forest } ss.

I Jean F. Resvick, do hereby certify that on the 23rd day of October, 1969, I found evidence of the South Center one sixteenth corner of Section 3 Township 40 North, Range 12 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Section subdivision survey by Ripco established this corner on line between the south quarter corner and the center quarter corner of section 3. Corner marked by a 1 inch outside diameter iron pipe with a 2 inch square brass plat welded on top stamped to identify corner.

Description of corner evidence found:


Found 1 inch diameter iron pipe with brass plate welded on top stamped to identify corner. From which the following bearing trees bear:

- Maple 8, bears N88W, 33.80 ft.
- Hemlock 14, stump, bears N54E, 41.60 ft.


Description of monument and accessories I established to perpetuate the original location of this corner:

Blazed and scribed the following new bearing tree:

- Balsam 11, bears N18E, 11.13 ft.



44012031020



● = Corner monument restored  
□ =

Resident witnesses \_\_\_\_\_

Dated at Rhinelander Wisconsin, this 23 day of January 1970.

Signature Jean F. Resvick Title Cadastral Surveyor  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802 DOCUMENT NUMBER 98061

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 22nd day of May 1970, and was filed in Book No. \_\_\_\_\_ Page No. D-15 of County Records.

Signature Eugene Stutzny Title Register of Deeds

Township 40 North, Range 12 East, Section 3, Index No. D-15, Page No. \_\_\_\_\_

015