

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }
 County of Forest } ss.

I, Jean F. Resvick, do hereby certify that on the 13th day of October, 1969, I found evidence of the Southwest 1/16 corner of Section 3 Township 40 North, Range 12 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Section subdivision survey by Ripco established location of corner.
 Corner marked by a railroad spike in the west edge of road.
 Bearing trees by Ripco.
 White pine 14, S68W, 25½ lks.
 White pine 8, S65E, 57½ lks.
 Iron pipe, 1 inch diameter with 2 inch square brass plate welded on top.
 Stamped 25 lks. East, 16.50 ft.

Description of corner evidence found:


Witness monument was brass plate stamped as recorded.
 Railroad spike in west edge of road, 16.50 ft. east of witness corner.
 White pine 14, S68W, 16.38 ft. (Later removed by road construction.)
 White pine 11, S65E, 38.00 ft.
 To protect this location from possible loss from road building I set hub N0° 21'E on 1/16 line 75.00 ft. for witness corner. I put nails with bottle caps in bearing tree at the distance recorded above. I put nail and bottle cap in white pine, NW of corner a distance of 52.66 feet.

I also blazed and scribed two new bearing trees as shown below.
 Description of monument and accessories I established to perpetuate the location of this corner:

On June 1, 1973 before road was surfaced I replaced hub set at N0°21'E, 75.00 ft. from corner with a 2 inch inside diameter galvanized iron pipe, 3 feet long, filled with concrete to weigh 5 pounds per foot with brass cap stamped witness corner ~~to~~ to identify corner.


From this and other witness established I set a 1 inch square iron bar, 18 inches long, 6 inches below surface of road. Top of bar punched to identify point measured too, from this point the following bearing trees bear:

- White pine 12, S72°05'E, 84.42 ft.
- White pine 11, S65°E, 38.00 ft.
- White pine 12, N80°42'W, 92.64 ft.
- White pine 18, northwest, 52.66 ft. (Not blazed or scribed.)



● = Corner monument restored
 □ =

Resident witnesses: _____
 Dated at Rhinelanders Wisconsin, this 27th day of July, 1973.
 Signature Jean F. Resvick Title Land Surveyor
 (County Surveyor, Registered Land Surveyor, or other duly authorized official)
 Surveyors Registration No. S-802 DOCUMENT NUMBER 104450



Office of Register of Deeds County of Forest
 I hereby certify that the within instrument was filed in this office for record on the 13th day of November, 1973, and was filed in Book Corner Restorations No. D-14 Page No. D-14 of County Records.

Signature Eugene Stutzman Title Register of Deeds

Township 40 North, Range 12 East, Section 3, Index No. D-14, Page No. _____

44012031030

0
174