

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin

County of Forest

ss.

DOCUMENT NUMBER

99451

I, Jean F. Resvick, do hereby certify that on the 22 nd day of September, 1970, I found evidence of the North Meander corner of Section 22 and 23 Township 40 North, Range 12 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Surveyed in 1859 by William E. Daugherty. Dependent Resurvey in 1941 by Guy R. Veal. From remains of original evidence, set a concrete monument, 2 feet long, 6 inches in diameter, 18 inches in the ground for meander corner of Sections 21 and 22 with an iron post 22 inches long, 1 inch in diameter, encased therein, with brass cap stamped to identify corner.

- Norway pine 18, bears N75E, 12 lks.
White pine stub 28, bears N33W, 5 lks.
Norway pine 13, 78 lks. (in SE quadrant)
White pine 10, N77W, 97 1/2 lks.

Description of corner evidence found:


- Iron pipe monument 3 feet long, 2 inches in diameter, 27 inches in ground with brass cap stamped to identify corner (recorded as concrete monument)
Norway 20, N75E, 7.90 feet
White pine stump, N33W, 3.3 feet
Norway pine 16, S70E, 51.5 feet
White pine (blow down, rotted) N77W, 64.5 feet

Description of monument and accessories I established to perpetuate the original location of this corner:

- Blazed and scribed the following new bearing tree
White Birch 6, S73W, 2.0 feet
Steel sign post with signs bears SE, 1.0 feet



44012221800



● = Corner monument restored
□ =

Resident witnesses

Dated at Rhinelander Wisconsin, this 2nd day of Nov. 1970.

Signature Jean F. Resvick Title Cadastral Surveyor
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 16th day of March 1971, and was filed in Book No. 1 Page No. P, Q-17 of County Records.

Signature Eugene Stegny Title Register of Deeds

Township 40 North, Range 12 East, Section 22, Index No. P, Q-17, Page No.

1017