

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin

County of Forest

ss.

I, Jean F. Resvick, do hereby certify that on the 2nd day of October, 1974, I found evidence of the Witness Point corner of Sections 25 and 26 Township 40 North, Range 14 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Dependent Resurvey of 1945 by H. B. Crawford  
 NO°31'W between Sections 25 and 26 21.18 chains intersect  
 South shore of Big Wapoose Lake. Set iron post, 3 feet long, 2 inches diameter, 28 inches in ground, for witness point, with brass cap marked: WP, S26, S25, 1945  
 Cedar 4, S83°15'E, 18 lks  
 Yellow Birch 6, S3W, 42 lks



Description of corner evidence found:

Monument as described  
 Cedar stump, scribed, S83°E, 17 lks  
 Yellow birch stump, scribed, S3W, 42 lks

Description of monument and accessories I established to perpetuate the location of this corner:

Blazed and scribed the following new bearing trees:  
 Spruce 3, S70°E, 14.57 feet  
 Tamarack 2, N11°E, 25.83 feet  
 Set steel sign post just west of monument

44014261200



● = Corner monument restored  
 □ =

Resident witnesses

Dated at Rhinelanders Wisconsin, this 20 day of March 1975

Signature Jean F. Resvick Title Land Surveyor  
 (County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802 Document Number 106888

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 31st day of March 1975, and was filed in Book No. Corner Page No. T, U-21 of County Records.

Signature Eugene Stutzman Title Register of Deeds

Township 40 North, Range 14 East, Section 25, Index No. T, U-21, Page No.

TU21