

## CERTIFIED LAND CORNER RESTORATION

State of Wisconsin

County of Forest

ss.

I Jean Resvick, do hereby certify that on the 8th day of September, 1970, I found evidence of the West quarter corner of Section 21 Township 41 North, Range 14 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

## Description of original monument and accessories and subsequent restorations:


Surveyed in 1865 by William Daugherty  
40 chains north between section 20 and 21, set post  
Birch 16, N62E, 16 lks.  
Birch 15, S84W, 20 lks.  
Brule River, North, 11.84 chains.

## Description of corner evidence found:

Squared cedar post in mound of rock bears S45E, 16.5 feet from a cedar with Forest Service location poster. Poster is dated 1936. Birch stump S84W, 6 feet from center of stump. This corner has been in place for nearly 40 years. I therefore accept the position as is as the best available evidence of the corner location.

## Description of monument and accessories I established to perpetuate the original location of this corner:

Replaced squared stake with a 2 inch inside diameter, galvanized, wrought iron pipe, 5 feet long, filled with concrete, flanged on bottom with brass cap marked



from which the following blazed and scribed new bearing trees bear.

Sugar 5, N48E, 16.65 ft.

Yellow Birch 16, N87E, 29.41 ft.

Cedar 8, S39W, 15.65 ft.

Steel post with sign 1 foot SW of monument

44114 20 2000

Resident witnesses.....

Dated at Rhineland Wisconsin, this 11th day of September 1970.

Signature Jean F. Resvick Title County Surveyor  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802

DOCUMENT No. 98925

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 23rd day of October 1970, and was filed in Book

No. CORNER Page No. P-9 of County Records.

Signature Eugene Stutzman Title Register of Deeds

Township 41 North, Range 14 East, Section 21, Index No. P-9, Page No.

● = Corner monument restored

□ =

