

State of Wisconsin  
County of FOREST

ss. ESTABLISHMENT OF QUARTER - QUARTER SECTION CORNER BETWEEN ORIGINAL GOVERNMENT SURVEY CORNERS.

I NEAL SPERHAKE, do hereby certify that on the TWENTY-NINTH day of OCTOBER, 19 63, I established the WEST ONE SIXTEENTH CORNER BETWEEN SECTIONS 11 AND 14, TOWNSHIP 34 NORTH, RANGE 13 EAST, Fourth Principal Meridian, as described hereon.

History: There is no record of this corner having ever been previously established.

Description of monument and accessories I established to perpetuate the location of this corner:


At the point determined for the location of the corner I emplaced a:

GALVANIZED IRON PIPE, THREE FEET LONG, ONE INCH IN DIAMETER, WITH ALUMINUM CAP DENOTED AS, "KIMBERLY CLARK CORP. T34N W 1/16 BTWN. 11 & 14 R13E SPERHAKE RLS 463 10/29/63."

The pipe is witnessed by:

- W. Birch 9 S 64°E 51½ links. (SCRIBED S14 BT).
- W. Birch 7 N 66°E 23 links. (SCRIBED S11 BT).

Description as to how corner was located: The section corner ¼ mile west has been previously established and the position of the quarter corner between 11 and 14 has been previously determined with a distance of 39.01½ chains between them. Thus, set the W 1/16 corner 19.50¾ chains from either corner and on a straight line between them.



0 = Corner monument restored

Subscribed & sworn to before me this 25 day of Aug 1964

Anna Peterson  
NOTARY PUBLIC, FOREST CO., WIS  
COM. EXPIRES 10/31/65

88959

Resident witnesses \_\_\_\_\_

Dated at Crandon, Wisconsin, this 25 day of Aug, 19 64.

Signature Neal Sperhake

Title Registered Land Surveyor Registration No. 463

Office of Reg. of Deeds County of Forest,  
I hereby certify that the within instrument was filed in this office for record on the 25 day of Aug 19 64, and was filed in Book No. \_\_\_\_\_ Page No. \_\_\_\_\_ of County Records.

Surveyor's Seal

Signature Anna Peterson Title Reg. of Deeds

43413 11 0030

Index No:

518  
118