

State of Wisconsin

County of FOREST

ss. RESTORATION OF LOST ORIGINAL GOVERNMENT SURVEY CORNER.

I NEAL SPERHAKE, do hereby certify that on the SEVENTEENTH day of SEPTEMBER, 19 64, I established the WITNESS CORNER TO THE CENTER QUARTER SECTION CORNER OF SECTION 14, TOWNSHIP 34 NORTH, RANGE 13 EAST, Fourth Principal Meridian, as described hereon.

History: There is no record of this corner having ever been previously established.

Description of monument and accessories I established to perpetuate the location of this corner:


At the point determined for the location of the corner I emplaced a:

GALVANIZED IRON PIPE, THREE FEET LONG, ONE INCH IN DIAMETER, WITH ALUMINUM CAP DENOTED AS, "KIMBERLY CLARK CORP. T34N C $\frac{1}{4}$ Section 14 WC - CORNER IS WEST 133.32 FEET - WC."

The pipe is witnessed by:

- Elm 6 S 8°W 24 links. (Scribed C $\frac{1}{4}$ S14 WC. BT).
- Elm 5 N 65°W 8 links. (Scribed C $\frac{1}{4}$ S14 WC. BT).

Description as to how corner was located: Two straight lines were run between the four previously established quarter section corners of this section. The intersection of the two lines, which is the position of the center quarter section corner, is in the lake at a point 38.99 chains-south of the north quarter section corner, 38.24 chains north of the south quarter section corner, 39.22 chains west of the east quarter section corner and 39.05 chains east of the west quarter section corner. The witness corner to the center of the section was then set on the east-west quarter line on the east bank of the lake, 133.32 feet east of the center of the section.



O = Corner monument restored

89573

REGISTRAR'S OFFICE
FOREST COUNTY, WIS.
FILE
JAN 12 1965
Anna Peterson, Register of Deeds

Resident witnesses _____

Dated at Crandon, Wisconsin, this 12 day of Jan., 19 65.

Signature Neal Sperhake

Title Registered Land Surveyor Registration No. 463

Office of County signed & sworn to, I hereby certify that the within instrument was filed in the office for record on the 12 day of Jan. 1965, and was filed in Book No. Page No. of County Records.

Surveyor's Seal

Signature Anna Peterson Title Notary Public

434131A2020

Index No. 1-19 619