

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }
County of Forest } ss.

I Jean F. Resvick, do hereby certify that on the 7 day of June, 1977, I found evidence of the Southwest Section corner of Section 34 Township 34 North, Range 15 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Surveyed in 1857 by Artemus Curtis
80.00 ch. West between Sections 3 and 34, set post
Hemlock 18, N25E, 40 lks.
Hemlock 14, S68E, 51 lks.
Hemlock 12, S40W, 42 lks.
Hemlock 18, N10W, 17 lks.


Description of corner evidence found:

1 1/4 inch iron rod in mound of stone, rod in old post hole.
Hemlock stump bears N25E, 40 lks.
Hemlock stump bears S68E, 55 lks.

Description of monument and accessories I established to perpetuate the location of this corner:

Replaced rod with 2 inch inside diameter galvanized iron pipe, 3 feet long, filled with concrete, with brass cap stamped; T34N, R15E, S33, S34, S4, S3, T33N, 1977, S-802

Maple 10, S73E, 16.40 ft.
Oak 13, S9E, 30.41 ft.
Maple 7, S66W, 44.86 ft.
Oak 10, N9W, 57.16 ft.
Set steel sign post 4 inches east of monument



● - Corner monument restored
□ -

Resident witnesses.....

Dated at Rhinelander Wisconsin, this 29 day of July 1977.

Signature *Jean F. Resvick* Title Land Surveyor
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802 DOCUMENT NUMBER 113283

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 13th day of February, 1978, and was filed in Book No. Page No. of County Records.

Signature *Eugene Stutzman* Title Register of Deeds

Township 34 North, Range 15 East, Section 34, Index No. Z-13, Page No.