

CERTIFIED LAND CORNER RESTORATION

Index No.

81


State of Wisconsin }
County of Forest } ss.

I Philip T. Hansen, do hereby certify that on the 11th day of August, 1975, I found evidence of the N-1/16 corner of Sections 1 and 6 Township 35, North, Range 11 and 12 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.


Resident witnesses:

Glen Barker

Jim Claflin



FORM 985 H. G. MILLER CO., MILWAUKEE



○ = Corner monument restored.

History of original corner establishment:

Corner of unknown origin recovered by John Macon, Consolidated Papers' Forester, in 1946. This was a wooden post scribed 1/8-1/8, set in a clump of small balsam. This is 58.13 chains north of the SW corner of Section 6.

Description of corner evidence found:

Recovered 4" cedar post, squared and scribed 1/8-1/8 in poor condition. No BT's were found. No records are on file in Forest or Oneida Counties. Based on the original length of this line and remeasured length in 1946, the true position of this corner should be south 1.48 chains but, because of the length of time, it has been accepted as the corner, 29 years plus, it was not reset.

Description of monument and accessories I established to perpetuate the original location of this corner.

Replaced 4" cedar post with 1-1/2" OD iron pipe w/2" brass cap stamped -

S498
T35N

NBT's: Black spruce 6" N23°W 20.7 links-scribed 1/16 BT
White spruce 6" S34°E 20.7 links-scribed 1/16 BT

R- R
11 S1 S6 12
E E
N-1/16
CPI-1975

Dated at Rhinelander, Wis., this 4th day of September, 1975

Signature *Philip T. Hansen* Title Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within instrument was filed in this office for record on the 6th day of October, 1975 at 1:00 o'clock P. M.

DOCUMENT NUMBER --- 107918

Eugene Staszynski
(Register of Deeds)
By _____ Deputy

43511013000