

State of Wisconsin

County of Forest

} ss.

ESTABLISHMENT OF EAST QUARTER - QUARTER SECTION CORNER OF SECTION 34

I, L. ERNEST GEORGE, do hereby certify that on the FIFTH day of AUGUST 1968, I established the EAST ONE SIXTEENTH CORNER ON THE EAST-WEST QUARTER LINE OF SECTION 34, TOWNSHIP 35 NORTH, RANGE 13 EAST, Fourth Principal Meridian as described hereon

History: There is no record of this corner having ever been previously established.

Description of monument and accessories I established to perpetuate the location of this corner:


At the point determined for the location of the corner, I emplaced a:

GALVANIZED IRON PIPE, THREE FEET LONG, ONE INCH IN DIAMETER, WITH ALUMINUM CAP DENOTED AS, "KIMBERLY-CLARK CORP. T35N E 1/16 of SEC. 34 R13E GEORGE RLS S-0309 8/5/68."

The pipe is witnessed by:

- Maple 5 S 11°E 51 links. (SCRIBED S34 BT).
- Maple 5 S 76°W 59½ links. (SCRIBED S34 BT).

Description as to how corner was located: The quarter corner ¼ mile east and the center ¼ of Section 34 ¼ mile west have been previously set with a distance of 40.27 chains between them. Thus set E 1/16th corner of Section 34, 20.13½ chains from either corner and on a straight line between them.



O = Corner monument restored

Resident witnesses _____

Dated at Crandon, Wisconsin, this 18th day of March, 1974.

Signature L. Ernest George

Title Registered Land Surveyor Registration No. S-0309

Office of Register of Deeds County of Forest, I hereby certify that the within instrument was filed in this office for record on the 19th day of March 1974, and was filed in Book No. Corner Restorations Page No. X-16 of County Records.

Surveyor's Seal

DOCUMENT NUMBER **105006**

Signature Eugene Stegny Title Register of Deeds

4351334 2010

Index No. **X16**