

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }
County of Forest } ss.

I Jean F. Resvick, do hereby certify that on the 5 day of May, 1977, I found evidence of the Southeast section corner of Section 13 Township 35 North, Range 15 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

- Surveyed in 1857 by Artemas Curtis
- 80.00 chains North between Sections 19 and 24, set post
- Yellow birch 14, S60W, 41 lks.
- Sugar 20, N70W, 34 lks.
- Yellow birch 10, N45E, 36 lks.
- Sugar 11, S82E, 50 lks.
- 11.50 chains North intersect stream 125 lks. wide runs SE
- 13.50 chains North leave stream
- 19.50 chains East, stream 250 lks. wide, runs SE

Description of corner evidence found:



- 1 1/2 inch steel pipe in mound of stone
- 11.6 ch. North river
- 19.5 ch. East river

Description of monument and accessories I established to perpetuate the location of this corner:

Replaced the iron pipe found with a 2 inch inside diameter galvanized iron pipe, 3 feet long, filled with concrete, with a brass cap stamped: T35N, R15E, R16E, S13, S18, S24, S19, 1977, S-802

Blazed and scribed the following new bearing trees:

- Maple 6, N66E, 26.34 feet
- Maple 8, N9W, 27.61 feet



● - Corner monument restored
□ -

Resident witnesses.....

Dated at Rhinelander Wisconsin, this 31 day of August 1977.

Signature Jean F. Resvick Title Land Surveyor
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802 DOCUMENT NUMBER 113294

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the.....day of.....19....., and was filed in Book No.....Page No.....of County Records.

Signature Eugene Stater Title Register of Deeds

Township 35 North, Range 15 East, Section 13, Index No. N-25, Page No.....