

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }  
County of Forest } ss.

I, Jean F. Resvick, do hereby certify that on the 28 day of March, 1977, I found evidence of the Southeast Section corner of Section 10 Township 35 North, Range 16 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Surveyed in 1858 by James McBride  
North between Sections 14 & 15. 80.0 chains set post corner to Sections 10, 11, 14, and 15.  
Lind, 12", N39°W, 38 lks.  
Fir, 10", N52°E, 44 lks.  
Lind, 8", S18°E, 23 lks.  
Elm, 10", S51°W, 43 lks.



Description of corner evidence found:

1 1/2 inch diam. pipe  
Basswood clump bears N39W, 38 lks.  
40.00 ch. east to found 1/4 corner  
40.00 ch. north to found 1/4 corner

Description of monument and accessories I established to perpetuate the location of this corner:

Replaced the iron pipe with a 2 inch inside diameter, galvanized pipe, 3 feet long with a brass cap stamped: T35N, R16E, S10, S11, S14, S15, 1977, S-802

From which the following bear:  
Maple, 20", N50°E, 40.60 feet  
Maple, 20", S16°E, 117.68 feet  
Hemlock, 20", S22°W, 107.80 feet  
Maple, 18", N19°W, 69.95 feet  
Steel sign post, NW, 0.50 feet



⊙ - Corner monument restored  
□ -

Resident witnesses.....

Dated at Rhinelander Wisconsin, this 21 day of July 1977.

Signature Jean F. Resvick Title Land Surveyor  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 13 day of Feb. 1975, and was filed in Book No. 113295 Page No. J-17 of County Records. 113295

Signature Eugene Stutzman Title Register of Deeds

Township 35 North, Range 16 East, Section 10, Index No. J-17, Page No. 113295

43516 100000

117