

CERTIFIED LAND CORNER RESTORATION

Index No. **J 9**


State of Wisconsin }  
County of Forest } ss.

I Philip T. Hansen, do hereby certify that on the 21st day of January, 1976, I found evidence of the Section corner of Secs. 8, 9, 16, & 17 Township 36 North, Range 14 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.


Resident witnesses:

Glen Barker

Jim Claflin



FORM 985 H. C. MILLER CO., MILWAUKEE



○ = Corner monument restored.

History of original corner establishment:

Original corner established by James McBride, Deputy Surveyor, in 1859 from which hemlock 14" bears S20°E, 11 links and sugar 14" bears N57°W, 21 links.

Corner recovered by Connor Forest Industries surveyor and maintained by Connor Foresters for many years.

Description of corner evidence found:

Recovered old 3" iron pipe with rock cairn at its base, projecting 2' above ground.

No definite old BT's - Sugar 30", S70°W, 30 links. Appeared to have been faced, but this was all rotted out, with no trace of scribe marks.

Description of monument and accessories I established to perpetuate the original location of this corner.

Replaced old 3" iron pipe with 2-1/2" Berntsen A-1 Federal Monument, aluminum, with magnet installed in cap and base. Cap stamped -

Pipe projects 18" above ground.

NBT's - Sugar 7" N1°E 51 links Scribed SC BT  
Sugar 10" S59°E 34.3 links Scribed SC BT  
Sugar 12" S17°W 43.3 links Scribed SC BT

T36N R14E  
Sec. 8 | 9  
17 | 16  
S498, 1976

Pipe and BT's painted blue.

Dated at Argonne, Wis., this 26th day of January, 1976.

Signature *Philip T. Hansen* Title Registered Land Surveyor Registration No. S-498  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within instrument was filed in this office for record on the 4th day of February, 1976, at 4:00 o'clock P. M.

*Eugene Staszny*  
(Register of Deeds)

By Deputy

DOCUMENT NUMBER 108708

4301408000