


CERTIFIED LAND CORNER RESTORATION

Index No. Y-24


State of Wisconsin }
County of Forest } ss.

I Daniel K. Pleoger, do hereby
certify that on the 25 day
of September, 19 81, I ~~found~~
Est. ~~evidence of~~ the SE 1/16
corner of Section 36
Township 37, North, Range
13 East, Fourth Principal Meridian,
as described hereon; and that from this evidence
I established a new monument and accessories
as described hereon to perpetuate the original
location of this corner.

Resident witnesses



FORM 985 K. C. MILLER CO., MILWAUKEE



○ = Corner monument restored.

History of original corner establishment:
No evidence of any previous corner

Description of corner evidence found:

Corner established by sub-division of the SE 1/4.
Location of SE 1/16 is S1-48-51W 1319.74 ft. of EC 1/16 and S88-10-51E 1311.069 ft.
of SC 1/16.

Description of monument and accessories I established to perpetuate the original location of this corner.

Set a 1 1/2" iron pipe with 2" diameter brass cap stamped:

S1537
T37N R13E
SE 1/16 S | 36
C.P.I. - 1981

Monument projects 18" above ground

Marked NBTs

Black spruce 5" N12W 31.70 ft.
Maple 5" N12E 42.10 ft.
Scribed 1/16 - B.T.

Dated at Rhineland, Wis., this 3rd day of November, 1981.

Signature Daniel K. Pleoger Title Registered Land Surveyor Registration No. 1537
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within
instrument was filed in this office for record on the 19th day of January, 1982.
at 3:00 o'clock P. M.

Eugene Staszynski
(Register of Deeds)

By _____ Deputy

DOCUMENT NO. **121085**

43713361010