

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }
County of Forest } SS.

I Jean Resvick, do hereby certify that on the 10th day of November, 1972, I found evidence of the South Quarter corner of Section 16 Township 38 North, Range 12 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:


Surveyed in 1859 by William Daugherty.
Dependent Resurvey by Wesson Cook in 1937
Proportionate location set 6 inch. diam. concrete monument, 24 inch. long with brass cap marked, 1/4. S16, S21, 1937
Hemlock 13, bears S54°30'E, 53 lks.
Yellow Birch 12, bears N18W, 164 lks.

Description of corner evidence found:

Concrete monument as described above
Hemlock 16 bears S52E, 34.50 ft.
Y. Birch 14, bears N18W, 108.30 ft.

Description of monument and accessories I established to perpetuate the location of this corner:

Blazed and scribed the following new bearing trees.
Balsam 8, bears N40E, 38.70 ft.
Balsam 8, bears S44W, 30.80 ft.
Iron sign post, bears North 1.0 ft.



● - Corner monument restored
□ -

Resident witnesses.....

Dated at Rhinelander Wisconsin, this 14th day of Dec. 1972.

Signature *Jean F. Resvick* Title Land Surveyor
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802 DOCUMENT NUMBER 102784

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 11th day of January 1973, and was filed in Book No. Page No. N-11 of County Records.

Signature *Eugene Staszny* Title Register of Deeds

Township 38 North, Range 12 East, Section 16, Index No. N-11, Page No.

43812160020

NT