

CERTIFIED LAND CORNER RESTORATION

Index No. N-11

State of Wisconsin }
County of Forest } ss.

I William B. Cochran, do hereby certify that on the 229th day of September, 1994, I found evidence of the South Quarter corner of Section 16 Township 39, North, Range 13 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

.....
.....
.....

History of original corner establishment:

Original Government Survey by William E. Daugherty in 1865.
West corrected between sections 16 and 21. At 40.09 chs set post.

Sugar 12" S56°W 33 lks
Sugar 8" N66°E 8 lks

In 1929 Melindy found wood post and bearing tree stump Maple S56°W 21.78'
New BT
Pine Stump 36" N88°E 83.00'


Description of corner evidence found:

Found melindys 1927 36" pine stump scribed 1/4, S88°W 83.00 feet no evidence of post. From recorded post position S56°W 21.78 ft found depression of possible maple stump hole.

Description of monument and accessories I established to perpetuate the original location of this corner.

From bearing and distance recored on melindys 1929 notes to the scribed 36" pine stump. Set a 2 1/2" X 36" aluminum pipe monument 2 1/2 feet in the ground with an aluminum cap stamped: T39N, R13E, 1/4, S16, S21, 1988, s-1107. From which:

Maple 12" N20°E 21.55'
Maple 14" S33°E 13.85'



● = Corner monument restored.

Dated at Hiles, Wis., this 12th day of December, 1994

Signature William B. Cochran Title Land Surveyor Registration No. S-1107
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Forest, I hereby certify that the within instrument was filed in this office for record on the 23rd day of August, 1996 at 2:30 o'clock P M.

(Register of Deeds)

By Paul Jankovics Deputy

FORM NO. 985-A



Stock No. 26273

156569

0200 0131654


Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (d), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing in (d), above.

See drawing below.

(f) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

Found perpetuated location and ties to original evidence.

(g&h) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location?



William B. Cochrane.

(i) I, _____ (type or print name) certify that the corner location shown on this record was determined by me or under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

William B. Cochrane 12/12/94
Signature Date

Survey requested by: _____
District Ranger Date