

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }
County of Forest } ss.

I Jean F. Resvick, do hereby certify that on the 23rd day of October, 1969, I found evidence of the Center quarter corner of Section 3 Township 40 North, Range 12 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Section subdivision survey by Ripco establish the location of center quarter corner. Corner marked by a 2 inch outside diameter iron pipe with a 3 inch square brass plate welded on top and stamped to identify corner.



Description of corner evidence found:

At a point N1°09'E, 2641.2 ft. from the south quarter corner of section 3 and S1°07'W, 2780.6 ft. from the north quarter corner of section 3 found 2 inch diameter iron pipe with 3 inch square brass plate stamped C1/4, S3, Ripco. From which a
White spruce 7 inch diameter, bears N83W, 19.55 ft.
White pine 11 inch diameter, bears S23E, 19.05 ft.

Description of monument and accessories I established to perpetuate the original location of this corner:

I did not add any new accessories.
True line was cut and blazed south to the south quarter corner and west to the west - center one sixteenth corner.

44012 03 2020



● = Corner monument restored
□ =

Resident witnesses _____

Dated at Rhinelander Wisconsin, this 22nd day of May 1970.

Signature Jean F. Resvick Title Cadastral Surveyor
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802 DOCUMENT Number 98064

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 22nd day of May 1970, and was filed in Book No. _____ Page No. C-15 of County Records.

Signature Eugene Stutzman Title Register of Deeds

Township 40 North, Range 12 East, Section 3, Index No. C-15, Page No. _____

C
15