

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }  
County of Forest } ss.

I Jean F. Resvick, do hereby certify that on the 21st day of October, 1969, I found evidence of the West center one sixteenth corner of Section 3 Township 40 North, Range 12 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Section subdivision survey by Ripco established location of corner. Corner marked by 1 inch outside diameter iron pipe with a 2 inch square brass plate welded on top which is stamped to identify corner.



Description of corner evidence found:

At a point N88°20'E, 1321.4 ft. from the west 1/4 corner of section 3 found 1 inch diameter iron pipe with 2 inch square brass plate stamped C-W1/16, Ripco. From which a blazed and scribed spruce 6 inch diameter, bears N11E, 9.50 feet. Center 1/4 section 3, bears N88°21'E, 1324.5 feet.

Description of monument and accessories I established to perpetuate the original location of this corner:

Blazed and scribed the following new bearing trees  
Balsam 7, double, bears S40°E, 53.34 ft.  
Balsam 7, bears S56°W, 25.48 ft.

44012032030



● = Corner monument restored  
□ =

Resident witnesses \_\_\_\_\_

Dated at Rhinelander Wisconsin, this 30th day of January 1970.

Signature Jean F. Resvick Title Cadastral Surveyor  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802 DOCUMENT NUMBER 98065

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 22nd day of May 1970, and was filed in Book No. \_\_\_\_\_ Page No. C-14 of County Records.

Signature Eugene Stutzman Title Register of Deeds

Township 40 North, Range 12 East, Section 3, Index No. C-14, Page No. \_\_\_\_\_

77