

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin }
County of Forest } ss.


DOCUMENT NUMBER 99452

I, Jean F. Resvick, do hereby certify that on the 22nd day of September, 1970, I found evidence of the North Quarter corner of Section 3, Township 40 North, Range 12 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner:

Description of original monument and accessories and subsequent restorations:

Surveyed in 1859 by Wm. E. Daugherty. Dependent Resurvey in 1941 by Guy R. Veal. On the 4th Standard Parallel North, and at proportionate distance based on the record of the original plat. Set a concrete monument, 2 feet long, 6 inches in diameter, 18 inches in the ground, for the 1/4 section corner of Section 3, only with a brass cap stamped: 1/4, S3, 1941. From which the following bear:
Maple, 18", bears S37E, 106 lks.
Maple, 12", bears S12W, 123 lks.
The standard corner of Sections 34 and 35 on the 4th standard parallel North, bears N89°57'E, 8.07 chains.

Description of corner evidence found:




Monument as described above.

Maple snag, 18" diameter, (blazed and scribed), bears S37E, 70 feet
The other bearing tree was not recovered. The standard corner of Sections 34 and 35, on the 4th standard parallel North, bears N89°57'E, 434.39 feet. (Recorded distance is 532.62 feet.)

Description of monument and accessories I established to perpetuate the original location of this corner:

Blazed and scribed the following new bearing trees:
Maple, 7", bears S77W, 6.37 feet
Maple, 7", bears S52E, 28.97 feet
Set a steel sign post North 0.90 feet with signs:



● = Corner monument restored
□ =

Resident witnesses.....

Dated at Rhinelander, Wisconsin, this 22nd day of Nov. 1970....

Signature *Jean F. Resvick* Title Cadastral Surveyor
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Surveyors Registration No. S-802.....

Office of Register of Deeds County of Forest

I hereby certify that the within instrument was filed in this office for record on the 16th day of March 1971, and was filed in Book No. 1 Page No. A-15 of County Records.

Signature *Eugene Stutzman* Title Register of Deeds

Township 40 North, Range 12 East, Section 3, Index No. A-15, Page No.

44012034020

A 15